

**Name of Work:- Work of Central plaza & VIP Parking at Shri. Mahalakshmi Jagdamba Sansthan,
Koradi**

Details of Items

Sr. No.	Description	Unit	Approximate Quantity	Rate in Rs.
	GROUND COVER			
1.	Sphagneticola trilobata (Wedelia Trilobe): Supplying ground cover, including loading at source ,transportation up to Koradi Dist. Nagpur, unloading ,stacking and planting etc. complete as directed by Engineer incharge.	No	500	
2.	Syngonium podophyllum (Syngonium Variegated) : Supplying ground cover, including loading at source ,transportation up to Koradi Dist. Nagpur, unloading ,stacking and planting etc. complete as directed by Engineer incharge.	No	500	
3.	Syngonium : Supplying ground cover, including loading at source ,transportation up to Koradi Dist. Nagpur, unloading ,stacking and planting etc. complete as directed by Engineer incharge.	No	300	
4.	Tradescantia zebrina : Supplying ground cover, including loading at source ,transportation up to koradi Dist. Nagpur, unloading, stacking and planting etc. complete as directed by Engineer incharge.	No	300	
5.	Ipomea chartreuse : Supplying ground cover, including loading at source, transportation up to Koradi Dist. Nagpur, unloading, stacking and planting etc. complete as directed by Engineer incharge.	No	300	
6.	Asparagus sprengeri : Supplying ground cover, including loading at source, transportation up to Koradi Dist. Nagpur, unloading, stacking and planting etc. complete as directed by Engineer incharge.	No	300	
7.	Asparagus meyeri : Supplying ground cover, including loading at source, transportation up to Koradi Dist. Nagpur, unloading, stacking and planting etc. complete as directed by Engineer incharge.	No	300	
8.	Verbena : Supplying ground cover, including loading at source, transportation up to Koradi Dist. Nagpur, unloading, stacking and planting etc. complete as directed by Engineer incharge.	No	300	
9.	Pandanus: Supplying ground cover, including loading at source, transportation up to Koradi Dist. Nagpur, unloading, stacking and planting etc. complete as directed by Engineer incharge.	No	500	
10.	Chlorophytum: Supplying ground cover, including loading at source, transportation up to Koradi Dist. Nagpur, unloading, stacking and planting etc. complete as directed by Engineer incharge.	No	500	
11.	Festuca glauca: Supplying ground cover, including loading at source, transportation up to Koradi Dist. Nagpur, unloading, stacking and planting etc. complete as directed by Engineer incharge.	No	300	
12.	Lavandula Lavender: Supplying ground cover, including loading at source, transportation up to Koradi Dist. Nagpur, unloading, stacking and planting etc. complete as directed by Engineer incharge.	No	250	
	Shrubs			
13.	Acalypha Hispida : Supplying shrubs (Minimum height atleast 2 to 3 feet feet above planter packet), including loading at source, transportation up to Koradi Dist. Nagpur, unloading, stacking and	No	200	

**Name of Work:- Work of Central plaza & VIP Parking at Shri. Mahalakshmi Jagdamba Sansthan,
Koradi**

Sr. No.	Description	Unit	Approximate Quantity	Rate in Rs.
	planting etc. complete as directed by Engineer incharge.			
14.	Acalypha wilkesiana Tricolor : Supplying shrubs (Minimum height atleast 2 to 3 feet above planter packet), including loading at source, transportation up to Koradi Dist. Nagpur, unloading, stacking and planting etc. complete as directed by Engineer incharge.	No	300	
15.	Allamanda neriifolia : Supplying shrubs (Minimum height atleast 2 feet above planter packet), including loading at source, transportation up to Koradi Dist. Nagpur, unloading, stacking and planting etc. complete as directed by Engineer incharge.	No	300	
16.	Calliandra emarginata : Supplying shrubs (Minimum height atleast 3 feet above planter packet), including loading at source, transportation up to Koradi Dist. Nagpur, unloading, stacking and planting etc. complete as directed by Engineer incharge.	No	300	
17.	Calliandra hybrida : Supplying shrubs (Minimum height atleast 5 feet and above, above planter packet), including loading at source, transportation up to Koradi Dist. Nagpur, unloading, stacking and planting etc. complete as directed by Engineer incharge.	No	300	
18.	Cestrum diurnum : Supplying shrubs (Minimum height atleast 3 feet and above, above planter packet), including loading at source, transportation up to Koradi Dist. Nagpur, unloading, stacking and planting etc. complete as directed by Engineer incharge.	No	250	
19.	Clerodendrum macrosiphon : Supplying shrubs (Minimum height atleast 1 feet and above, above planter packet), including loading at source, transportation up to Koradi Dist. Nagpur, unloading, stacking and planting etc. complete as directed by Engineer incharge.	No	200	
20.	Daedalacanthus macrophyllus : Supplying shrubs (Minimum height atleast 2 feet and above, above planter packet), including loading at source, transportation up to Koradi Dist. Nagpur, unloading, stacking and planting etc. complete as directed by Engineer incharge.	No	250	
21.	Euphorbia cotinifolia: Supplying shrubs (Minimum height atleast 3 feet and above, above planter packet), including loading at source, transportation up to Koradi Dist. Nagpur, unloading, stacking and planting etc. complete as directed by Engineer incharge.	No	300	
22.	Excoecaria bicolor: Supplying shrubs (Minimum height atleast 2 feet and above, above planter packet), including loading at source, transportation up to Koradi Dist. Nagpur, unloading, stacking and planting etc. complete as directed by Engineer incharge.	No	200	
23.	Gardenia jasminoides: Supplying shrubs (Minimum height atleast 2 to 3 feet, above planter packet), including loading at source, transportation up to Koradi Dist. Nagpur, unloading, stacking and planting etc. complete as directed by Engineer incharge.	No	200	

**Name of Work:- Work of Central plaza & VIP Parking at Shri. Mahalakshmi Jagdamba Sansthan,
Koradi**

Sr. No.	Description	Unit	Approximate Quantity	Rate in Rs.
24.	Ixora chinensis: Supplying shrubs (Minimum height atleast 1 to 1.5 feet above planter packet), including loading at source, transportation up to Koradi Dist. Nagpur, unloading, stacking and planting etc. complete as directed by Engineer incharge.	No	100	
25.	Ixora coccinea: Supplying shrubs (Minimum height atleast 3 feet and above, above planter packet), including loading at source, transportation up to Koradi Dist. Nagpur, unloading, stacking and planting etc. complete as directed by Engineer incharge.	No	150	
26.	Ixora Singaporensis: Supplying shrubs (Minimum height atleast 3 feet and above, above planter packet), including loading at source, transportation up to Koradi Dist. Nagpur, unloading, stacking and planting etc. complete as directed by Engineer incharge.	No	100	
27.	Lagerstroemia indica Candida: Supplying shrubs (Minimum height atleast 3 feet and above, above planter packet), including loading at source, transportation up to Koradi Dist. Nagpur, unloading, stacking and planting etc. complete as directed by Engineer incharge.	No	200	
28.	Lagerstroemia indica Rosea: Supplying shrubs (Minimum height atleast 3 feet and above, above planter packet), including loading at source, transportation up to Koradi Dist. Nagpur, unloading, stacking and planting etc. complete as directed by Engineer incharge.	No	300	
29.	Lagerstroemia lancasteri: Supplying shrubs (Minimum height atleast 3 feet and above, above planter packet), including loading at source, transportation up to Koradi Dist. Nagpur, unloading, stacking and planting etc. complete as directed by Engineer incharge.	No	200	
30.	Mussaenda erythrophylla Rosea: Supplying shrubs (Minimum height atleast 3 feet and above, above planter packet), including loading at source, transportation up to Koradi Dist. Nagpur, unloading, stacking and planting etc. complete as directed by Engineer incharge.	No	150	
31.	Mussaenda erythrophylla Scarlet: Supplying shrubs (Minimum height atleast 3 feet and above, above planter packet), including loading at source, transportation up to Koradi Dist. Nagpur, unloading, stacking and planting etc. complete as directed by Engineer incharge.	No	200	
32.	Nikotia leucophyllum: Supplying shrubs (Minimum height atleast 3 feet and above, above planter packet), including loading at source, transportation up to Koradi Dist. Nagpur, unloading, stacking and planting etc. complete as directed by Engineer incharge.	No	200	
33.	Punica granatum flore-pleno: Supplying shrubs (Minimum height atleast 3 feet, above planter packet), including loading at source, transportation up to Koradi Dist. Nagpur, unloading, stacking and planting etc. complete as directed by Engineer incharge.	No	200	
34.	Tabernaemontana coronaria: Supplying shrubs (Minimum height atleast 3 feet, above planter packet), including loading at source, transportation up to Koradi Dist. Nagpur, unloading, stacking and planting etc. complete as directed by Engineer incharge.	No	300	



**Name of Work:- Work of Central plaza & VIP Parking at Shri. Mahalakshmi Jagdamba Sansthan,
Koradi**

Sr. No.	Description	Unit	Approximate Quantity	Rate in Rs.
35.	Tabernaemontana coronaria Variegata: Supplying shrubs (Minimum height atleast 3 feet, above planter packet), including loading at source, transportation up to Koradi Dist. Nagpur, unloading, stacking and planting etc. complete as directed by Engineer incharge.	No	250	
36.	Tecoma gaudichaudi: Supplying shrubs (Minimum height atleast 3 feet and above, above planter packet), including loading at source, transportation up to Koradi Dist. Nagpur, unloading, stacking and planting etc. complete as directed by Engineer incharge.	No	250	
37.	Tecoma capensis: Supplying shrubs (Minimum height atleast 3 feet, above planter packet), including loading at source, transportation up to Koradi Dist. Nagpur, unloading, stacking and planting etc. complete as directed by Engineer incharge.	No	250	
38.	Thunbergia erecta: Supplying shrubs (Minimum height atleast 2 to 3 feet, above planter packet), including loading at source, transportation up to Koradi Dist. Nagpur, unloading, stacking and planting etc. complete as directed by Engineer incharge.	No	300	
	HEDGES	No		
39.	Duranta repens: Supplying hedges (Minimum height atleast 2 feet, above planter packet), including loading at source, transportation up to Koradi Dist. Nagpur, unloading, stacking and planting etc. complete as directed by Engineer incharge.	No	200	
40.	Duranta repens Variegata: Supplying hedges (Minimum height atleast 2 feet, above planter packet), including loading at source, transportation up to Koradi Dist. Nagpur, unloading, stacking and planting etc. complete as directed by Engineer incharge.	No	300	
41.	Duranta repens Golden: Supplying hedges (Minimum height atleast 2 feet, above planter packet), including loading at source, transportation up to Koradi Dist. Nagpur, unloading, stacking and planting etc. complete as directed by Engineer incharge.	No	250	
42.	Murraya exotica: Supplying hedges (Minimum height atleast 3 feet and above, above planter packet), including loading at source, transportation up to Koradi Dist. Nagpur, unloading, stacking and planting etc. complete as directed by Engineer incharge.	No	200	
43.	Justicia panduraefolia: Supplying hedges (Minimum height atleast 3 feet and above, above planter packet), including loading at source, transportation up to Koradi Dist. Nagpur, unloading, stacking and planting etc. complete as directed by Engineer incharge.	No	250	
	TREES	No		
44.	Millingtonia hortensis : Supplying trees (Minimum height atleast 14 feet above planter packet, 5" to 9" trunk's circumference and bag size 25" x 25"), including loading at source, transportation up to Koradi Dist. Nagpur, unloading, stacking and planting etc. complete as directed by Engineer incharge.	No	150	

**Name of Work:- Work of Central plaza & VIP Parking at Shri. Mahalakshmi Jagdamba Sansthan,
Koradi**

Sr. No.	Description	Unit	Appoximate Quantity	Rate in Rs.
45.	Peltophorum pterocarpum (Yellow Gulmohar) : Supplying trees (Minimum height atleast 14 feet above planter packet, 5" to 9" trunk's circumference and bag size 25" x 25"), including loading at source, transportation up to Koradi Dist. Nagpur, unloading, stacking and planting etc. complete as directed by Engineer incharge.	No	150	
46.	Bauhinia blackeana Purpurea : Supplying trees (Minimum height atleast 14 feet above planter packet, 5" to 9" trunk's circumference and bag size 25" x 25"), including loading at source, transportation up to Koradi Dist. Nagpur, unloading, stacking and planting etc. complete as directed by Engineer incharge.	No	200	
47.	Bauhinia blackeana Alba: Supplying trees (Minimum height atleast 14 feet above planter packet, 5" to 9" trunk's circumference and bag size 25" x 25"), including loading at source, transportation up to Koradi Dist. Nagpur, unloading, stacking and planting etc. complete as directed by Engineer incharge.	No	150	
48.	Cassia javanica: Supplying trees (Minimum height atleast 14 feet above planter packet, 5" to 9" trunk's circumference and bag size 25" x 25"), including loading at source, transportation up to Koradi Dist. Nagpur, unloading, stacking and planting etc. complete as directed by Engineer incharge.	No	150	
49.	Millettia ovalifolia: Supplying trees Supplying trees (Minimum height atleast 14 feet above planter packet, 5" to 9" trunk's circumference and bag size 25" x 25"), including loading at source, transportation up to Koradi Dist. Nagpur, unloading, stacking and planting etc. complete as directed by Engineer incharge.	No	150	
50.	Plumeria alba: Supplying trees (Minimum height atleast 10 feet above planter packet, 5" to 9" trunk's circumference and bag size 21" x 21"), including loading at source, transportation up to Koradi Dist. Nagpur, unloading, stacking and planting etc. complete as directed by Engineer incharge.	No	150	
51.	Plumeria rubra: Supplying trees (Minimum height atleast 10 feet above planter packet, 5" to 9" trunk's circumference and bag size 21" x 21"), including loading at source, transportation up to Koradi Dist. Nagpur, unloading, stacking and planting etc. complete as directed by Engineer incharge.	No	150	
52.	Lagerstroemia speciosa : Supplying trees (Minimum height atleast 14 feet above planter packet, 5" to 9" trunk's circumference and bag size 25" x 25"), including loading at source, transportation up to Koradi Dist. Nagpur, unloading, stacking and planting etc. complete as directed by Engineer incharge.	No	150	
53.	Terminalia catappa: Supplying trees (Minimum height atleast 14 feet above planter packet, 5" to 9" trunk's circumference and bag size 25" x 25"), including loading at source, transportation up to Koradi Dist. Nagpur, unloading, stacking and planting etc. complete as directed by Engineer incharge.	No	150	

**Name of Work:- Work of Central plaza & VIP Parking at Shri. Mahalakshmi Jagdamba Sansthan,
Koradi**

Sr. No.	Description	Unit	Approximate Quantity	Rate in Rs.
54.	Spathodea campanulata: Supplying trees (Minimum height atleast 14 feet above planter packet, 5" to 9" trunk's circumference and bag size 25" x 25"), including loading at source, transportation up to Koradi Dist. Nagpur, unloading, stacking and planting etc. complete as directed by Engineer incharge.	No	200	
55.	Mimusops elengi: Supplying trees (Minimum height atleast 14 feet above planter packet, 5" to 9" trunk's circumference and bag size 25" x 25"), including loading at source, transportation up to Koradi Dist. Nagpur, unloading, stacking and planting etc. complete as directed by Engineer incharge.	No	150	
56.	Casuarina equisetifolia: Supplying trees (Minimum height atleast 14 feet above planter packet, 5" to 9" trunk's circumference and bag size 25" x 25"), including loading at source, transportation up to Koradi Dist. Nagpur, unloading, stacking and planting etc. complete as directed by Engineer incharge.	No	150	
57.	Erythrina indica Picta (Parijat): Supplying trees (Minimum height atleast 14 feet above planter packet, 5" to 9" trunk's circumference and bag size 25" x 25"), including loading at source, transportation up to Koradi Dist. Nagpur, unloading, stacking and planting etc. complete as directed by Engineer incharge.	No	150	
58.	Callistemon lanceolatus (Bottle brush Red): Supplying trees (Minimum height atleast 14 feet above planter packet, 5" to 9" trunk's circumference and bag size 25" x 25"), including loading at source, transportation up to Koradi Dist. Nagpur, unloading, stacking and planting etc. complete as directed by Engineer incharge.	No	200	
59.	Anthocephalus Cadamba (Kadam): Supplying trees (Minimum height atleast 14 feet above planter packet, 5" to 9" trunk's circumference and bag size 25" x 25"), including loading at source, transportation up to Koradi Dist. Nagpur, unloading, stacking and planting etc. complete as directed by Engineer incharge.	No	150	
60.	Putranjiva roxburghii (Putranjiva Jivanputra): Supplying trees (Minimum height atleast 14 feet above planter packet, 5" to 9" trunk's circumference and bag size 25" x 25"), including loading at source, transportation up to Koradi Dist. Nagpur, unloading, stacking and planting etc. complete as directed by Engineer incharge.	No	200	
61.	Melaleuca bracteata (Golden Bottle Brush): Supplying trees (Minimum height atleast 14 feet above planter packet, 5" to 9" trunk's circumference and bag size 25" x 25"), including loading at source, transportation up to Koradi Dist. Nagpur, unloading, stacking and planting etc. complete as directed by Engineer incharge.	No	200	
62.	Terminalia mantaly (Madagascar Almond): Supplying trees (Minimum height atleast 14 feet above planter packet, 5" to 9" trunk's circumference and bag size 25" x 25"), including loading at source, transportation up to Koradi Dist. Nagpur, unloading, stacking and planting etc. complete as directed by Engineer incharge.	No	200	

**Name of Work:- Work of Central plaza & VIP Parking at Shri. Mahalakshmi Jagdamba Sansthan,
Koradi**

Sr. No.	Description	Unit	Appoximate Quantity	Rate in Rs.
63.	Barringtonia acutangula: Supplying trees (Minimum height atleast 14 feet above planter packet, 5" to 9" trunk's circumference and bag size 25" x 25"), including loading at source, transportation up to Koradi Dist. Nagpur, unloading, stacking and planting etc. complete as directed by Engineer incharge.	No	200	
64.	Magnolia: Supplying trees (Minimum height atleast 14 feet above planter packet, 5" to 9" trunk's circumference and bag size 25" x 25"), including loading at source, transportation up to Koradi Dist. Nagpur, unloading, stacking and planting etc. complete as directed by Engineer incharge.	No	200	
65.	Terminalia arjuna: Supplying trees (Minimum height atleast 14 feet above planter packet, 5" to 9" trunk's circumference and bag size 25" x 25"), including loading at source, transportation up to Koradi Dist. Nagpur, unloading, stacking and planting etc. complete as directed by Engineer incharge.	No	150	
66.	Ficus benghalensis (Vad): Supplying trees (Minimum height atleast 14 feet above planter packet, 5" to 9" trunk's circumference and bag size 25" x 25"), including loading at source, transportation up to Koradi Dist. Nagpur, unloading, stacking and planting etc. complete as directed by Engineer incharge.	No	200	
67.	Ficus religiosa (Pipal): Supplying trees (Minimum height atleast 14 feet above planter packet, 5" to 9" trunk's circumference and bag size 25" x 25"), including loading at source, transportation up to Koradi Dist. Nagpur, unloading, stacking and planting etc. complete as directed by Engineer incharge.	No	200	
68.	Hardwickia binata: Supplying trees (Minimum height atleast 14 feet above planter packet, 5" to 9" trunk's circumference and bag size 25" x 25"), including loading at source, transportation up to Koradi Dist. Nagpur, unloading, stacking and planting etc. complete as directed by Engineer incharge.	No	200	
69.	Azadirachta indica (Neem): Supplying trees (Minimum height atleast 14 feet above planter packet, 5" to 9" trunk's circumference and bag size 25" x 25"), including loading at source, transportation up to Koradi Dist. Nagpur, unloading, stacking and planting etc. complete as directed by Engineer incharge.	No	200	
70.	Mimosops Hexandra (Khirmi): Supplying trees (Minimum height atleast 14 feet above planter packet, 5" to 9" trunk's circumference and bag size 25" x 25"), including loading at source, transportation up to Koradi Dist. Nagpur, unloading, stacking and planting etc. complete as directed by Engineer incharge.	No	150	
	TOPIARY			
71.	Adansonia digitata: Supplying trees (Minimum height atleast 10 feet above planter packet), including loading at source, transportation up to Koradi Dist. Nagpur, unloading, stacking and planting etc. complete as directed by Engineer incharge.	No	100	

**Name of Work:- Work of Central plaza & VIP Parking at Shri. Mahalakshmi Jagdamba Sansthan,
Koradi**

Sr. No.	Description	Unit	Approximate Quantity	Rate in Rs.
72.	Couroupita guianensis Cannonball tree: Supplying trees (Minimum height atleast 10 feet above planter packet), including loading at source, transportation up to Koradi Dist. Nagpur, unloading, stacking and planting etc. complete as directed by Engineer incharge.	No	100	
73.	Bougainvillea: Supplying trees (Minimum height atleast 3 feet above planter packet), including loading at source, transportation up to Koradi Dist. Nagpur, unloading, stacking and planting etc. complete as directed by Engineer incharge.	No	100	
74.	Ficus racemosa Cluster fig: Supplying trees (Minimum height atleast 10 feet above planter packet), including loading at source, transportation up to Koradi Dist. Nagpur, unloading, stacking and planting etc. complete as directed by Engineer incharge.	No	100	
75.	Ficus triangularis variegata: Supplying trees (Minimum height atleast 5 feet above planter packet), including loading at source, transportation up to Koradi Dist. Nagpur, unloading, stacking and planting etc. complete as directed by Engineer incharge.	No	100	
	PALM			
76.	Royal Palm: Supplying trees (Minimum height atleast 10 feet above planter packet, bag size 25" x 25"), including loading at source, transportation up to Koradi Dist. Nagpur, unloading, stacking and planting etc. complete as directed by Engineer incharge.	No	200	
77.	Phoenix Palm: Supplying trees (Minimum height atleast 8 feet above planter packet, bag size 25" x 25"), including loading at source, transportation up to Koradi Dist. Nagpur, unloading, stacking and planting etc. complete as directed by Engineer incharge.	No	200	
78.	Cycus Revoluta: Supplying trees (Minimum height atleast 3 to 4 feet above planter packet, full grown plant), including loading at source, transportation up to Koradi Dist. Nagpur, unloading, stacking and planting etc. complete as directed by Engineer incharge.	No	200	
79.	Rhapis: Supplying trees (Minimum height atleast 6 feet above planter packet, bag size 25" x 25"), including loading at source, transportation up to Koradi Dist. Nagpur, unloading, stacking and planting etc. complete as directed by Engineer incharge.	No	200	
80.	Livinstonia Chinensis: Supplying trees (Minimum height atleast 6 feet above planter packet, bag size 25" x 25"), including loading at source, transportation up to Koradi Dist. Nagpur, unloading, stacking and planting etc. complete as directed by Engineer incharge.	No	200	
81.	Hyophorbe lagenicaulis: Supplying trees (Minimum height atleast 5 feet above planter packet and bag size 25" x 25"; Minimum height atleast 6 feet above planter packet and bag size 30" x 30"), including loading at source, transportation up to Koradi Dist. Nagpur, unloading, stacking and planting etc. complete as directed by Engineer incharge.	No	200	
82.	Bismarckia nobilis: Supplying trees (Minimum height atleast 6 feet above planter packet, bag size 25" x 25"), including loading at source, transportation up to Koradi Dist. Nagpur, unloading, stacking and planting etc. complete as directed by Engineer incharge.	No	200	

**Name of Work:- Work of Central plaza & VIP Parking at Shri. Mahalakshmi Jagdamba Sansthan,
Koradi**

Sr. No.	Description	Unit	Appoximate Quantity	Rate in Rs.
SPRINKLERS & ACCESSORIES				
83.	Providing & fixing Pop-up ROTOR sprinkler having 3/4" INLET & variable adjustable arc (50 to 360 degrees)nozzle capable of covering 4.9m -14.0 m at 2.5 Bars with discharge rate of 0.02- 0.891Lps.The Rotor body, stem, nozzle and screen shall be constructed of heavy-duty, ultraviolet resistant plastic with small exposed cover. (Make-Hunter/Rain Bird)	Nos	150.00	
84.	Providing & fixing of Pop up spray head bodies, having 1/2" INLET features an encased plastic 'cage' to provide unmatched resistance to grit,with high efficiency ADJUSTABLE nozzle capable of covering 1.2M -5.2m at 1.0 - 2.1 Bars, pressur. Additionally Two-piece ratchet mechanism, Features is Precision controlled flush at pop-down clears debris from unit, Construction of time-proven UV_resitant plastic. (Make - Hunter/Rain Bird)	Nos	150.00	
85.	Providing & fixing of Rotatory Pop up having 1/2" INLET colour coded nozzle with multiple stream water spray capable of covering 2.5m- 10.7m with Matched Precipitation Rate .The Spray Head body shall be constructed of heavy-duty, ultraviolet resistant plastic and stainless steel spring with multifunctional wiper seal with small exposed cover. (Make - Hunter/Rain Bird)	Nos	150.00	
86.	Providing & fixing of Pop-up ROTOR sprinkler having 1" INLET & variable adjustable arc (50 to 360 degrees)nozzle capable of covering 11.9m -21.6 m at 4.0 Bars with discharge rate of 0.23- 2.01Lps.The Rotor body, stem, nozzle and screen shall be constructed of heavy-duty, ultraviolet resistant plastic with small exposed cover. (Make - Hunter/Rain Bird)	Nos	45.00	
87.	Providing & Fixing of SJ- 512, 1/2" Pop up Connecting Four Elbow Swing joint Assembly. The fittings shall be made of UV resistant thermo plastic.	Nos	150.00	
88.	Providing & Fixing of SJ- 712, 3/4" Pop up Connecting Four Elbow Swing joint Assembly. The fittings shall be made of UV resistant thermo plastic. (Make - Hunter/Rain Bird)	Nos	75.00	
89.	Providing & Fixing of 1" Pop up Connecting Swing joint Assembly.The fittings shall be made of UV resistant thermo plastic. (Make - Automat/Rain Bird)	Nos	50.00	
90.	Providing and fixing of PP service saddle of varying size.	Nos	275.00	
DRIP LATRAL AND ACCESSORIES				
91.	Supply and fixing of flexible Inline tubing and resistance to UV damage and algae growth black in colour 16 mm size. With all fittings and accessories. (Make - Jain/Supreme)	Rm	4200.00	

**Name of Work:- Work of Central plaza & VIP Parking at Shri. Mahalakshmi Jagdamba Sansthan,
Koradi**

Sr. No.	Description	Unit	Approximate Quantity	Rate in Rs.
92.	Supply and fixing of Plain lateral flexible Blank tubing and resistance to UV damage and algae growth black in colour 16 mm size. With all drippers, fittings and accessories. (Make - Jain/Supreme)	Rm	4200.00	
VALVES & ACCESSORIES				
93.	Providing and fixing of PVC Ball Valve, security pivot to maintain lever in space, double water tight joint, direct injection stem non mechanical, with a base which permits maximum penetration into the valve of size 63mm. (Make - Automat/Jain)	Nos	20.00	
94.	Providing & fixing of a double acting 1" Air release valve, The Air release valve shall be capable of both releasing and admitting air from and into the line. The working pressure shall be 5 bar. Including service saddle and riser assembly. (Make - Automat/Jain)	Nos	2.00	
95.	Providing & fixing of 12" Rectangular Valve Box with green lid and corrugated structure with unique shovel access slot and bolt hole knockout (Make - Hunter/Rain Bird)	Nos	10.00	
96.	Providing & fixing of 6/ 10" Round box with green lid and corrugated structure with unique shovel access slot and bolt hole knockout (Make - Hunter/Rain Bird)	Nos	15.00	
97.	Providing & fixing of Brass Quick coupling valve made up of solid brass with locking cover corrosion resistant and stainless steel spring. Including service saddle and riser assembly. (Make - Automat/Jain)	Nos	10.00	
98.	Providing & fixing of Brass Key threads into top of QCV to provide water access And Brass Swivel Elbow (Make - Automat/Jain)	Nos	10.00	
FILTRATION UNIT				
99.	Providing & Fixing of Disc Filter with capacity matching pump design flow having an suitable inlet connections, to create a helical effect in the incoming water, spinning particulate in suspension away from the filtering element and so minimizing cleanings frequency, 3/4" outlet for flushing at bottom of filter & maximum working pressure of 10 Bars. with pressure gauge. (Make - Automat/Jain)	Nos	2.00	
100.	Fertilizer application unit:- 1 1/2" Rotameter Venturi with Suction Port and assembly (Make - Automat/Jain)	Nos	1.00	
PUMPING UNIT				
101.	Providing & Fixing of Monobloc or openwell submersible pumpset of having discharge 7 lps@68 mtr head. (Make - Deccan/LHP)	Nos	2.00	
102.	Providing and fixing of control panel suitable for TWO pumpset having panel box and fixed along with following accessories starter, start / stop push buttons, Ammeter, Voltmeter, Indicating lamps, MCB, with cable, etc.	Nos	1.00	

**Name of Work:- Work of Central plaza & VIP Parking at Shri. Mahalakshmi Jagdamba Sansthan,
Koradi**

Sr. No.	Description	Unit	Approximate Quantity	Rate in Rs.
103.	Providing & Fixing of Suction ,Delivery & Header Pipe	Nos	2.00	
104.	Providing & fixing of control Valve /Butterfly Valve in mainline for bypass and flow diversion of approved quality 2 1/2" (Make - Normax/Equivalent)	Nos	2.00	
105.	Providing & fixing of Non Return Valve to prevent back flow 2 1/2" (Make - Normax/Equivalent)	Nos	1.00	
106.	Providing and fixing of Pressure Release Valve (Make - Automat/Jain)	Nos	1.00	
	DECODER Equipment			
107.	Supply and fixing of Direct burial 14 AWG x 2C Decoder cable for two way communication between decoder controller and decoders with PVC conduit Pipe complete (Make - Hunter/Rain Bird)	Mtr	800.00	
108.	Supply and fixing of DECODER CONTROLLER, upto 99 STATION CAPACITY, outdoor mount with 230/240 VAC internal transformer decoder control system, 99 station decoder output module with outdoor plastic cabinet to support sensor decoder,turf decoders and line surgeprotectors with options of program BACK UP AND RESTORE , cycle +soak, Raindelay, SOLARSYNC Mini weather station, controlling upto 2 master valve with diagnostic feature in wire shorttest ,voltage test at stations, and with option to upgradable to central control including , standard accessories complete (Make - Hunter/Rain Bird)	No	1.00	
109.	Supply and fixing of 1-STATION DECODER FOR USE WITH ANY ACC DECODER CONTROLLER, INCLUDES 2 WATERPROOF CONNECTORS (Make - Hunter/Rain Bird)	Nos	10.00	
110.	Supply and fixing of 2" Solenoid globe Valves with fabric reinforced diaphragm and rugged PVC construction ,compatible with and slow closing to prevent water hammer,pressure rating upto 10 bar with 24AC solenoid, with provision to attach Pressure Regulator (Make - Hunter/Rain Bird)	Nos	10.00	
111.	Supply and fixing of ACCUSINC to Maintain constant outlet pressure between 1.5 to 7 bar. (Make - Hunter/Rain Bird)	Nos	1.00	
112.	Supply and fixing of direct bury -on wire connector with strain relief , with waterproof silicon sealant. (Make - Hunter/Rain Bird)	Nos	20.00	
113.	Supply and fixing of copper grounding rod, clamps, charcoal and all requisite accessories complete	Nos	2.00	
114.	Supply and fixing of Rain Sensor with latching bracket and extension wire complete (Make - Hunter/Rain Bird)	Nos	2.00	
115.	Supply and fixing of Pump relay 24 AC PLA relay (Make - Hunter/Rain Bird)	Nos	2.00	

**Name of Work:- Work of Central plaza & VIP Parking at Shri. Mahalakshmi Jagdamba Sansthan,
Koradi**

Sr. No.	Description	Unit	Appoximate Quantity	Rate in Rs.
116.	Supply & fixing Kirlosker pump SKU: PU.MO.286449Head (m): 40 - 50Warranty Months: 12Impeller Material: BronzeProduct Code: D11010501520Power (HP): 5Phase: SingleType of Product: Non - Self Priming Monoblock PumpDischarge (LPM): 250 - 120Model No: KDS-550++ 5.0 HPSuc x Del (mm): 50 x 40Motor Body: Cast IronPower At Heavy Duty (kW): 3.7 with all necessary accessories & fittings etc, complete as directed by Engineer Incharge.	Nos	1.00	
	Total Amount			