

Nagpur Metropolitan Region Development Authority

QUOTATION NOTICE

Nagpur Improvement Trust/NMRDA has declared as a Nodal Agency for carrying out the work of Renovation & Modification of Existing Museum, Beautification of Site and Construction of proposed Building at 'SHANTIVAN', Chicholi, Nagpur.

NMRDA invites sealed quotations on Item rate basis from Reputed agencies, Registered contractors for following twelve items. The brief descriptions of Items with drawings are available at NMRDA's website www.nmrda.org.

General Description

Item No.	Item Details	Quantity
1.	Providing and laying Glass mosaic tiles on dome surface at various heights, (Pearl make or equivalent) of size 25mm x 25mm x 4mm (chips applied on paper of size 330mm x330mm) of Gold & White colour..... including all etc. complete.	543.06 M ²
2.	Supplying, fitting & fixing Stainless steel railing height of 1m. from floor finish level of 304 grade & coil of brand Mukund/ Jindal including all etc. complete.	146.40 M ²
3.	Providing and applying oil paint to the decorative columns, clay tiles, beams using Duco make primer , one coat of Duco make yellow oil paint , two coats of weatherproof gold colour, two coats of lacer of duco brand..... including all etc. complete.	964.08 M ²
4.	Providing and fixing Fibre Reinforced Plastic Band at dome bottom area 500 mm width comprising of hallow sections made of 6mm thick FRP as per the photograph and drawings including all etc. complete.	161.62 M ²
5.	Supplying and laying true to line and level high grip, scratch resistant neutral to UV rays, full body rock deck vitrified tiles or equivalent conforming to IS:15622-2006 & IS 4457-2007 including all etc. complete.	2215.00 M ²
6.	Design, Supply, Fabrication and Erection of suitable tensile membrane structure including all necessary fixing arrangements, in (built up sections) including all etc. complete.	839.84 M ²
7.	Providing and Fixing wooden Pargola as Conopy containing perscape sections, tie beams: 140mm x 42mm, posts: 95mmx95mm , 115mmx 115mm, rhombus element c7: 68mmx 26mm, design as per the drawings provided by the architect including all etc. complete.	150.00 M ²
8.	Providing and fixing wooden deck/ floor and steps as per the drawings provided by architect including all etc. complete.	240.00 M ²
9.	Providing and Fixing Bronze Metal sculputre art work of 0.60 m height angle statue in bronze metal 4 mm thick, fixing on cast iron lamp post, as per drawing including all etc. complete.	50.00 Nos.
10.	Providing and Fixing Fibre Reinforced Polymer murals of 1m x1 m size 6mm thick FRP and art work depth upto 100 mm as per the photograph and drawings including all etc. complete.	100.00 M ²
11.	Providing and fixing Bronze statue art work of 0.90 m height burst statue of Wamanraoji Godbole in bronze metal 4 mm thick, as per drawing including all etc. complete.	1.00 No.
12.	Providing and Installation of Cast Iron ornamental lamp post of size 200 mm at bottom and 75mm at top with two lamps on two sides, with 4 m height, as per drawings including all etc. complete.	100.00 Nos.

The sealed quotations in physical form of submission will be received upto 2.00 p.m. on **13.07.2018** at the office of the Superintending Engineer(Project), Gokulpeth Market, Dharampeth, Nagpur-10 and will be opened on **13/07/2018** at 3.00 p.m. or as decided by NIT.

The agencies will have to write name of work & name of agency on sealed envelopes of quotations. The rates will be used for inviting tenders and work will be executed through tender only.

The brief descriptions of Items with drawings are available at NIT's website www.nmrda.org. The rates will be used for inviting tenders and work will be executed through online e-tender process only.

-Sd-
Superintending Engineer(HQ)
Nagpur Metropolitan Region Development
Authority

Advt. No. S.E. NMRDA/ 36.

Dated : 05/07/2018.